

BECKER COUNTY MATERIAL RECOVERY
 BUILDING ADDITION
 24413 CO RD 144
 DETROIT LAKES, MN



MBA PROJECT NO. 18052

ADDENDUM NO. 4

Bid Packages Covered by This Addendum:
 SINGLE PRIME CONTRACTOR

December 2, 2021

Acknowledge receipt of this Addendum by inserting its number in space provided on Bid Form. Failure to do so may subject Bidder to disqualification. This Addendum forms part of Bidding Documents and modifies them as follows.

SPECIFICATIONS

Section 03 3000 – Cast in Place Concrete

- 03 3000-2, Add paragraph 2.08, Concrete Sealer, Concrete Sealer to be Siloxa-Tek 8505 or equal, install per manufacturer's recommendations.

The following additions, deletions and / or changes shall be made to the DRAWINGS:

Sheet M1.0 Mechanical Demolition, Schedules, Symbols, And Specifications

- Refer to attached sheet R2/M1.0 for revised fan schedule.

FAN SCHEDULE										
FAN ID	TYPE	CFM	ESP (INCH)	HP	VOLTAGE/ PHASE	DRIVE	SONES	ECM	MANUFACTURER & MODEL	NOTES
EF-1	PROP	9,300	0.75	3	480/3	DIRECT	46	Y	GREENHECK AER-E30C-415-VG	2,4,5,7
EF-2	IL	675	0.5	1/4	120/1	DIRECT	12.3	Y	GREENHECK SQ-99-VG	1,3,4
EF-3	PROP	4,100	0.75	2	480/3	DIRECT	28	Y	GREENHECK AER-E20C-620-VG	2,4,5,6,7
EF-4	IL	300	0.5	1/10	120/1	DIRECT	8.7	Y	GREENHECK SQ-80-VG	1,3,4,6

<ol style="list-style-type: none"> PROVIDE WITH VIBRATION ISOLATORS. PROVIDE CO DETECTION SYSTEM AND INTERLOCK WITH FAN. PROVIDE WITH DISCONNECT SWITCH FACTORY MOUNTED AND WIRED. PROVIDE WITH BACKDRAFT DAMPER. PROVIDE WITH WALL SLEEVE, MOTOR GUARDS, AND WEATHER HOOD. PROVIDE UNDER ALTERNATE M-1. OMIT UNDER BASE BID. PROVIDE WITH STARTER/DISCONNECT. 	PROP-PROPELLER IL-INLINE
-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-----------------------------

END OF ADDENDUM NO. 4