

# Memo

To: Becker County Demolition Landfill Cell Construction Bidders  
From: Steve Skoog, Becker County Land Use Department Director  
CC: Brian Shepard, Becker County Highway Department  
Greg Smith, WSN  
Date: October 6, 2021  
Re: Addendum to Bid Form for Construction Contract, Becker County Demolition Landfill

---

Clarification to Bid Documents:

Alternate #1:

- All topsoil shall be removed from the fill area and stockpiled nearby prior to placement of the clay fill. The stockpiled topsoil shall be spread along the west bank of the filled area and then seeded with grass seed and mulched and disk anchored with Type 1 Straw Mulch.
- No off-road equipment may be used to haul soil on bituminous roads. The maximum load limit on bituminous roads is per Minnesota Statue and shall be approved by the Becker County Highway Engineer.

Stockpiled fill

- All stockpiled soil shall be sloped and seeded; the seeded surface shall be leveled and graded prior to seeding. The soil shall be mulched and disk anchored with Type 1 Straw Mulch. The maximum slope shall be 3:1 slope. All stockpiled soils shall have a minimum of four inches of acceptable topsoil (4") placed prior to seeding.

Seed specification for Alternate #1 and the stockpiled soils shall be as per bid specifications.

- Seeding of the covered cell will be with DOT seed mixture 25-151.

Each bidder shall provide a list of machinery they will be using for this project (including possible machine work to be completed per Becker County request) and the per hour rate for the machine and operator with the bid documents.